



TROCKNUNGSTECHNIK FRIEDRICH GMBH



OUR RECOMMENDATIONS

In order to carry out the best possible drying process after water damage, there are a few points that you should bear in mind. Please take a look at our 9 recommendations on the back of this flyer.

**Do you have any questions about restoration
or the further procedure?**

Please contact [SAGA](#) directly.



Trocknungstechnik Friedrich GmbH
An der Strusbek 32b
22926 Ahrensburg

E-Mail: info@trocknungstechnik-friedrich.de
Web: www.trocknungstechnik-friedrich.de



9 RECOMMENDATIONS FOR SUCCESSFUL DRYING

BEFORE DRYING

1. DELICATE FURNISHINGS

Remove delicate objects such as antique solid wood furniture, green plants, musical instruments (especially those made of wood) and bottles with corks from the room to be dried and store them temporarily if necessary.

2. FLOOR COVERINGS

We will not repair or replace floor coverings, such as tiles, carpets or PVC, that have to be drilled through in the course of the drying work. Please inform your household contents insurance about this. Neither we at Trocknungstechnik Friedrich nor the owner or the building insurance will pay for this!

3. DOORS AND WINDOWS

Keep doors and windows closed in all affected rooms and areas during the drying process. Of course, you should continue to air rooms regularly, preferably for 10 minutes three times a day.

4. DEVICE OPERATION

Leave all drying appliances running continuously. If the noise of an appliance deprives you of sleep at night, you can switch it off and switch it on again as soon as you get up in the morning. However, this will extend the drying time, which may result in additional costs.

5. COLLECTION CONTAINER (EMPTYING)

Empty the water collection containers in the drying appliances regularly, approx. 1 to 2 times a day. For safety reasons, the appliances switch themselves off automatically when the collection containers are full. The drying process is interrupted.

6. DRYING TIME

As a rule, assume a drying period of 14 to 21 days, which ends with a final measurement. This measurement confirms the success of the drying process.

7. ELECTRICITY CONSUMPTION

The electricity Consumption will be reimbursed by us. Please provide us with the German bank details of the main tenant. Our technician will provide a corresponding form. You are also welcome to enter your bank details conveniently online (simply scan the QR code).



8. DRILL HOLES

Be sure that we have all the core drill holes that we have drilled for drying, temporarily sealed with corks. This protects them well until the redecoration work begins.

9. RESTORATION

Redecoration can begin as soon as the final measurement has been successfully carried out. Please contact SAGA for the restoration.

DURING THE DRYING PROCESS

AFTER DRYING